



NOTES:

1. STREET TREE SHALL BE A SPECIES FROM THE CITY APPROVED TREE LIST. CONTACT THE OFFICE OF THE URBAN FORESTER AT (831) 420-5270 FOR MORE INFORMATION.
2. MAINTAIN 5' MINIMUM CLEARANCE BETWEEN GRATE OPENING AND BACK OF WALK.
3. CONTRACTOR SHALL REMOVE NURSERY STAKE(S) AND TAGS FROM TREES UPON COMPLETION OF STAKING.
4. AS DIRECTED BY THE CITY THE TREE GRATE SHALL BE A CAST IRON NEENAH FOUNDRY CO. NO. R8710 (48" x 48") WITH U-FRAME AND ACCESS HOLE.
5. TREE WELL SHALL BE IRRIGATED WITH BUBBLER HEAD AND A QUICK COUPLER EVERY 100'.
6. TREES TO BE INSPECTED AND APPROVED BY URBAN FORESTER - BEFORE AND AFTER PLANTING.
7. CONTRACTOR SHALL REMOVE ALL WIRE, STRING AND NURSERY WRAPS.
8. LEAVE SUBGRADE UNDISTURBED TO PROVIDE A FIRM BASE FOR ROOTBALL
9. SHAPE SOIL SURFACE TO PROVIDE WATERING RING.
10. ADJUST TREE TIES TO ALLOW ROOM FOR GROWTH DURING ESTABLISHMENT (ALLOW SLACK).
11. INSTALLATION INCLUDES REMOVAL OF STAKES 1-2 YEARS AFTER INSTALLATION (OR WHEN TREE TRUNK IS THE SAME DIAMETER AS THE TREE STAKE).



CITY OF SANTA CRUZ
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

TREE PLANTING DETAIL IN STREET RIGHT-OF-WAY

CITY ENGINEER: _____

DATE: MARCH 2025

SCALE: N.T.S.

DWG NO. G8